




Site2Cloud

ACE Team

Aviatrix Multicloud Network Architecture






Site2Cloud Introduction

IPsec connection to Public Cloud:


- On-Prem DC
- Branch
- 3rd Party Appliances, SD-WAN
- Clouds Native Constructs (VPCs/VNets/VCNs)





Site2Cloud Solution


- Easy to use and templatedriven
- Built-in diagnostic tools
- Solves Overlapping IPs Challenges



Site2Cloud Landing Options

Aviatrix Controller

- Landing on Transit
 - Extend Core
 - SD-WAN
- Landing on Spoke
 - Scale
 - Partners
 - Complex Overlapping IP
 - Advanced NAT capabilities



Site2Cloud – Deployment



BGP is supported on Site2Cloud tunnels to External Connections (S2C) Native Peering either Transit Gateway or Spoke Gateway Q Sea + External Connection **BGP Settings** Δ Ⅲ Φ Create External Connection to External Device Tunnel Type Local Gateway Remote Gateway IP BGP over IPsec 35.178.213.109 ACE-ONPREM-DC ace-aws-eu-west-1-transit1 S2C-PARTNER S2C-PARTNER Static Route-Based (Mapped) ace-gcp-us-east1-spoke1 18.133.109.111 Connect Using Type ○ BGP ○ Static-Route Based ○ Static-Policy Based Mapped Custom Mapped O Off Connect Using Type Connect overlapping networks between the cloud and on-premises from a Transit, Spoke, or Specialty Gateway. ■ BGP ○ Static-Route Based ○ Static-Policy Based Run BGP over an IPsec connection from a Transit or BGP Spoke Gateway. IPSec Real Local Subnet CIDR(s) Virtual Local Subnet CIDR(s) Local Gateway ace-gcp-us-east1-spoke1 172.16.211.0/24 × 192.168.1.0/24 × GRE Local Gateway LAN Real Remote Subnet CIDR(s) Virtual Remote Subnet CIDR(s) Remote Gateway Type Generic 172.16.211.0/24 × 192.168.2.0/24 × IKEv2 Over Private Network Algorithms Advanced Settings Authentication Method Connect Using Type O PSK O Certificate ○ BGP ○ Static-Route Based ○ Static-Policy Based Mapped Over Private Network IKEv2 Algorithms Default Custom Mapped O Off O Off O Default O Custom On Mapped Connect overlapping networks between the cloud and on-premises from a T Active Mesh Tunnel Configuration ① Single IP HA + Re Local Gateway Real Local Subnet CIDR(s) Virtual Local Subnet CIDR(s) Remote Gateway IP Local Gateway Instance Local Tunnel IP Remote Tunnel IP Pre-Shared Key Remote Gateway Type Real Remote Subnet CIDR(s) Virtual Remote Subnet CIDR(s) 18.130.247.103 169.254.0.1/30 169.254.0.1/30 ace-gcp-us-e ... ~ Generic


Cancel




Monitoring & Troubleshooting Site2Cloud

Connectivity Diagnostics





- Tunnel is operational?
- 'Current' number is increasing on both ends
 - CoPilot> Networking > Connectivity > External Connections (S2C) > Connectivity Diagnostics
 - Make sure SPI (Security Parameter Index) matches on remote end
 - SPI is an identification tag added to the header while using IPsec for tunneling the IP traffic
 - SPI is required part of an IPSec Security Association (SA)
 - https://en.wikipedia.org/wiki/Security_Paramet er Index






Monitoring – SPI

AVIATRIX ACE AVIATRIX CERTIFIED ENGINEER

Cisco IOS outcome

```
OnPrem-Partner#show crypto ipsec sa interface tu1
interface: Tunnel1
   Crypto map tag: Tunnel1-head-0, local addr 172.16.211.36
  protected vrf: (none)
   local ident (addr/mask/prot/port): (0.0.0.0/0.0.0.0/0/0)
   remote ident (addr/mask/prot/port): (0.0.0.0/0.0.0.0/0/0)
  current_peer 34.139.73.146 port 4500
    PERMIT, flags={origin_is_acl,}
   #pkts encaps: 8, #pkts encrypt: 8, #pkts digest: 8
   #pkts decaps: 8, #pkts decrypt: 8, #pkts verify: 8
   #pkts compressed: 0, #pkts decompressed: 0
   #pkts not compressed: 0, #pkts compr. failed: 0
   #pkts not decompressed: 0, #pkts decompress failed: 0
   #send errors 0, #recv errors 0
    local crypto endpt.: 172.16.211.36, remote crypto endpt.: 34.139.73.146
    plaintext mtu 1422, path mtu 1500, ip mtu 1500, ip mtu idb GigabitEthernet1
    current outbound spi: 0xC1B5E56C(3249923436)
    PFS (Y/N): N, DH group: none
    inbound esp sas:
     spi: 0x81432F90(2168663952)
       transform: esp-256-aes esp-sha256-hmac ,
       in use settings ={Tunnel UDP-Encaps, }
       conn id: 2001, flow_id: CSR:1, sibling_flags FFFFFFF80000048, crypto map: Tunnel1-head-0
       sa timing: remaining key lifetime (sec): 2021
       Kilobyte Volume Rekey has been disabled
       IV size: 16 bytes
       replay detection support: Y
       Status: ACTIVE(ACTIVE)
      spi: 0x3A53A9B9(978561465)
       transform: esp-256-aes esp-sha256-mm
       in use settings ={Tunnel UDP-Encaps, }
       conn id: 2004, flow_id: CSR:4, sibling_flags FFFFrr-50000048, crypto map: Tunnel1-head-0
```

Aviatrix CoPilot outcome



SPI matches on both ends





Monitoring – 'Current' number is increasing



Aviatrix CoPilot outcome – First Time

Aviatrix CoPilot outcome - Second Time





'Current' number is increasing



Troubleshooting



In the event of an IPsec VPN tunnel going down, follow these steps in sequence:

- 1. Confirm Layer 3 connectivity
 - Public IP reachable? Is there an ISP (BGP) issue?
 - If ping is disabled, check packet capture on remote public IP for ISAKMP packets
- 2. Confirm SG/NSG allowed for outbound
 - UDP 500 (ISAKMP for ESP)
 - UDP 4500 (NAT- Traversal)
- 3. Confirm whether IPsec Phase 2 or IPsec SA negotiation is stuck
 - Restart IPsec service from SITE2CLOUD > Diagnostics
- 4. Check policies outside each end of the tunnel
 - ACL policies on remote end
 - Security Groups/NACLs on Cloud side

Supported IPsec Encryption Algorithms




Туре	Value		
Phase 1 Authentication	SHA-1, SHA-512, SHA-384, SHA-256		
Phase 1 DH Groups	1, 2, 5, 14, 15, 16, 17, 18, 19, 20, 21		
Phase 1 Encryption	AES-256-CBC, AES-256-GCM-64, AES-256-GCM-96, AES-256-GCM-128, AES-192-CBC, AES- 128-CBC, AES-128-GCM-64, AES-128-GCM-96, AES-128-GCM-128, 3DES		
Phase 2 Authentication	HMAC-SHA-1, HMAC-SHA-512, HMAC-SHA-384, HMAC-SHA-256, NO-AUTH		
Phase 2 DH Groups	1, 2, 5, 14, 15, 16, 17, 18, 19, 20, 21		
Phase 2 Encryption	AES-128-CBC, AES-192-CBC, AES-256-CBC, AES-256-GCM-64, AES-256-GCM-96, AES-256-GCM-128, AES-128-GCM-64, AES-128-GCM-96, AES-128-GCM-128, 3DES, NULL-ENCR		

https://docs.aviatrix.com/HowTos/site2cloud_faq.html



Diagnostics - Run Analysis







Analysis – On-prem router is down



On-prem router is down...



Analysis Last Run: Jan 31, 2024 12:50 AM Run Tunnel analysis for connection s2c-partner: Tunnel ace-gcp-us-east1-spoke1<-->3.11.235.99: ISAKMP Phase 1 SA is not established. Possible reasons: 1. Peer gateway not reachable (IP address incorrect or blocked) 2. Peer gateway not reachable over UDP port 500




Analysis – UDP port 500 is not permitted



Security group rule ID ▽	IP version	▼ Type	▽ Protocol	▽ Port range	▽ Source
sgr-0176887910548ab41	IPv4	Custom UDP	UDP	4500	0.0.0.0/0
sgr-00e743fbe80ad493f	IPv4	All ICMP - IPv4	ICMP	All	0.0.0.0/0
sgr-0befa511b6d1e85f5	IPv4	SSH	ТСР	22	0.0.0.0/0





Analysis – Pre-shared key mismatch



```
crypto ikev2 keyring OnPrem-Aviatrix
peer OnPrem-Aviatrix
address 34.139.73.146
identity address 34.139.73.146
pre-shared-key WRONG
!
```



```
Analysis

Last Run: Jan 31, 2024 1:01 AM

Run

Tunnel analysis for connection s2c-partner:

Tunnel ace-gcp-us-east1-spoke1<-->3.11.235.99: ISAKMP Phase 1 SA is not established. Possible reasons:

1. IPSEC Phase 1 authentication method is not pre-shared key
2. Pre-shared key mismatch
3. IPSEC remote id mismatch
```

Analysis – DH Group mismatch



```
OnPrem-Partner#show crypto ikev2 proposal
```

IKEv2 proposal: avx-s2c

Encryption : AES-CBC-256

Integrity : SHA256
PRF : SHA256

DH Group : DH_GROUP_1536_MODP/Group 5



```
Analysis

Last Run: Jan 31, 2024 1:10 AM

Run

Tunnel analysis for connection s2c-partner:

Tunnel ace-gcp-us-east1-spoke1<-->3.11.235.99: IPsec Phase 2 SA is not established. Possible reasons:

1. Encryption/Authentication algorithm mismatch
2. DH group number mismatch
```



Analysis – Encryption algorithm mismatch




Aviatrix CoPilot outcome

Cisco IOS outcome

```
OnPrem-Partner#show crypto ipsec transform-set
Transform set default: { esp-aes esp-sha-hmac }
  will negotiate = { Transport, },

Transform set OnPrem-Aviatrix: { esp-256-aes esp-md5-hmac }
  will negotiate = { Tunnel, },


OnPrem-Partner#
```





Diagnostics – show logs







Dead Peer Detection Mismatch



• Dead Peer Detection is configured on Aviatrix gateways by default as follows (can be

Clear Sessions

configured):

- interval 10 seconds
- retry 3 times
- · max failure 3 times
- If DPD is disabled on remote end:
 - Disable it on Site2Cloud gateway from Networking > Connectivity > S2C conn. > Settings
 - Restart the VPN service from Networking > Connectivity > S2C conn. > Connectivity Diagnostics



NOTE:

Clear

- This will restart all tunnels on this gateway
- Could impact your service till the tunnels come up

BGP Troubleshooting




PATH: CoPilot> Networking > Connectivity > External Connections (S2C) > BGP Diagnostics





BGP Troubleshooting – List of commands








BGP Troubleshooting – show running






23

BGP Troubleshooting – show ip bgp







Edge



Introducing Aviatrix Edge



The only multi-cloud native platform with enterprise-grade visibility and control for public cloud and the edge

Aviatrix software in multiple form factors providing consistent network, security, and visibility to the edge. Edge locations appear and behave as another VPC/VNET with spoke and transit capabilities.



Cloud Out Architecture




Simplified Edge Management



Consistent Secure Edge




Simplified Edge On-boarding






Aviatrix Edge Use Cases










Edge 2.0 Deployment Workflow - Demo







BGP Route Approval





BGP Route Approval

AVIATRIX
ACE

AVIATRIX CERTIFIED
ENGINEER

- Can explicitly approve any BGP-learned route from Partner or on-prem into the cloud network
- Prevents unwanted advertisement of routes such as 0/0
- New routes arrive at Aviatrix Transit GW
- 2. Transit GW reports new routes to Controller
- Controller notifies admin via email
- 4. Admin accesses the Controller to approve
- 5. If approved, Controller programs the new routes to Spoke VPCs








BGP Route Approval – Activation



PATH: CoPilot > Cloud Fabric > Gateways > select the relevant Gateway > Settings
 > Border Gateway Protocol (BGP)






BGP Route Approval – Verification



PATH: CoPilot > Cloud Fabric > Gateways > select the relevant Gateway






BGP Route Approval – Config – Pre-Approved CIDRs



PATH: CoPilot > Cloud Fabric > Gateways > select the relevant Gateway > Approval



- This feature allows to pre-approving CIDRs advertised by external networks.
- The CIDRs will be propagated without the administrator logs into the CoPilot




Site2Cloud & CoPilot



Site2Cloud Visibility via CoPilot



PATH: COPILOT > Diagnostics > Cloud Routes > Site 2 Cloud








Site2Cloud BGP via CoPilot

PATH: COPILOT > Diagnostics > Cloud Routes > BGP Info









Show BGP Map


Show BGP Learned Routes



Site2Cloud Sessions via CoPilot



PATH: COPILOT > Cloud Fabric > Topology > select the relevant Gateway > Diagnostic Tools







Next: Lab 6 Site2Cloud

